

# Tequesta Country Club

Established 1959  
Restored 2013





Tequesta Country Club was originally designed by Dick Wilson in 1958. It was built on a similar sand ridge as Jupiter Hills just to the North.

The photo below was taken in 1958 and was used as a guide to our 2013 restoration.

The original irrigation was a single center row metal pipe with a greens loop.

In 2012, we replaced the existing wet well, flume, pump station, electrical components and rebuilt the pump house. H.D.P.E. was used to replace the failing metal and a VFD pumping system was installed. This was an essential pre-renovation decision due to the aggressive construction & grow-in schedule.

Rainbird ICS, HDPE piping was installed by Leibold Irrigation. A 3 row system with half heads along perimeter grass lines included 1000 sprinklers heads.



New HDPE Wet well



Existing Wet Well



Existing Flume

New HDPE Flume





April of 2013 we started Round-up applications and construction began on May 1, 2013.

Prior to our renovation, we had a variety of mutations in our bermuda and struggled to maintain any type of grass under trees.

We were also having mud balls due to the heavy organic matter build up over 54 years of neglect.

A highway asphalt grinder was used to successfully rototill the entire course and the old asphalt cart paths. A minimum of 16" depth blended the natural white sand with the existing organic.





Before







Pre Construction  
Maintained turf  
108 ac

Tequesta Country Club 2008

Scale 1"=300'



# Tequesta Country Club



After





Hole 12 Tee Complex  
Natural Scrub Planting  
Process





Water usage has been reduced by an average of 100,000 gallons per day. Reduced turf grass and maintenance has realized more man hours to playable areas. The difficulty of the course increased to lower handicapped golfer while decreasing to higher handicapped golfers by a higher handicap rating and a lower slope rating. A daily construction schedule and detailed budget was created and followed to precise accuracy that included an on budget and on time opening.

